



GENERAL NOTES

- Min. Concrete Strength: 30 MPa @ 28 Days
- Manufactured in accordance with CSA A23.4
- Custom Bolt Square & Bolts Available
- Site Installation, Backfilling & Suitability for use is the responsibility of others



POLE BASE - TYPE L2

DRAWN BY: AY	DIMENSIONS IN MILLIMETERS UNLESS OTHERWISE SPECIFIED	DWG #: PB
DATE: 27-Aug-13	TOLERANCES ± 5	L2